Location	Desc	Estimated Size of Available land (SF)	Estimated Lot Size	Required Access to Trail	Right-of-Way Assessment	LOW LOT Construction Cost	High LOT Construction Cost	LOW PE COST	HIGH PE COST	Total Est. Cost Range without Right-of-Way		
Broadway	Broadway: The Town owns a four-acre property on Turner Avenue adjacent to the proposed trail that is undeveloped, and it is across the street from a park, ideal for parking.	90,720	100	Sidewalk exists to trail site. Crosswalk and ADA facilities will need to be provided across Turner Ave	Property is owned by Town of Broadway. No R/W is anticipated	\$ 3,200,000.00	\$ 4,000,000.00	\$ 800,000.00	\$ 1,000,000.00	\$4.0M - 5.0M		
Timberville	The Town's park master plan includes a trailhead where the rail line intersects with Memorial Park Drive.	Park has adequate space	Spaces Needed ee. Large trailhead will be Broadway	20' trail connection would need to be provided from road to trail	Connection is within the R/W of the trail alignment	\$ 12,000.00	\$ 13,000.00	\$ 12,000.00	\$ 13,000.00	\$24K - \$26K		
Timberville	Another option is where North Main Street intersects the rail line.	2,500	5	Trailhead will have direct access	Area is within the R/W of the trail alignment. Possible permanent and temporary easements may be required	\$ 115,000.00	\$ 150,000.00	\$ 100,000.00	\$ 75,000.00	\$0.2M - \$0.3M		
New Market	New Market Depot Road (needs to be parallel parking)	6,000	10	Trailhead will have direct access	Area is within the R/W of the trail alignment. Possible permanent and temporary easements may be required	\$ 230,000.00	\$ 300,000.00	\$ 100,000.00	\$ 150,000.00	\$0.3M - \$0.5M		
Quicksburg	There may be space for a handful of cars parked where Village Lane meets the rail corridor.		Spaces Needed d parking	30' trail connection would need to be provided from road to trail	Connection is within the R/W of the trail alignment	\$ 13,000.00	\$ 15,000.00	\$ 13,000.00	\$ 15,000.00	\$26K - \$30K		
Mount Jackson	Mount Jackson's Town Hall was designed and built to mimic a train station. The Town has a parking lot ready to go and a visitor center right on the tracks. Other town-owned sites have been identified for potential overflow parking.	No Additional Spaces Needed overflow parking has been identified and on-street parking is available Trailhead will have direct access										
Edinburg	Town's historic 1848 Edinburg Mill	No additional	spaces needed	Needs trail connection via stairs behind graveyard. Not ADA accessible	The Mill owns property on the easterr side Massie Farm Ln. R/W will be needed north of the Cedarwood Cemetery Line	\$ 240,000.00	\$ 346,000.00	\$ 120,000.00	\$ 173,000.00	\$0.4M-\$0.6M		
Edinburg	Adjacent to the rail crossing on Stony Creek Blvd right before the trail bridge over Stony Creek (wide siding)	4,800	12	Trailhead will have direct access. ADA Accessible location	Area is within the R/W of the trail alignment. Possible permanent and temporary easements may be required	\$ 300,000.00	\$ 360,000.00	\$ 150,000.00	\$ 180,000.00	\$0.4M-\$0.6M		
Woodstock	The intersection of the rail trail and Court Street, a scenic mid-point, would offer close access to and from Interstate 81 and Route 11. The Town of Woodstock is adding public parking to this location with additional public land for expansion.	13,000	30	Trailhead will have direct access. Sidewalk facilities exist on Court Street. ADA Accessible location	Property is owned by Town of Woodstock. No R/W is anticipated	\$ 960,000.00	\$ 1,200,000.00	\$ 480,000.00	\$ 600,000.00	\$1.4M - 1.8M		
Strasburg	Although parking is limited, this downtown trailhead would complement the King Street streetscape improvements in-progress very nicely.	7,000	14	Trailhead will have direct access. ADA Accessible location	Property is own by the Museum	\$ 322,000.00	\$ 420,000.00	\$ 161,000.00	\$ 210,000.00	\$0.4M - \$0.6M		
Town Park	this site could serve as the eastern gateway to Strasburg	No Additional	Spaces Needed	A crosswalk and ADA facilities would be required to access from the front of the park to where the trail intersects Park Road	All improvements would be within public R/W					-		
Front Royal	the VDOT district office adjoins the rail corridor and can serve as a temporary trailhead until a larger property is secured across the South Fork.	· ·	s Needed - Temporary Alternate Site	A trail connection and footbridge would need to be provided	Connection is within the R/W of the trail alignment	\$ 241,000.00	\$ 394,000.00	\$ 300,000.00	\$ 600,000.00	\$700K - \$1.0M		
Front Royal	This site is located between Queens Highway and Old Winchester Pike. It is west of the trail termini. As well as on the west side of the South Fork of the Shenandoah River.	32000	75	Trailhead would be immediately abutting the trail	Connection is within the rail alignment right-of-way	\$ 2,400,000.00	\$ 3,000,000.00	\$ 600,000.00	\$ 750,000.00	\$3.0M - \$3.8M		
Front Royal	Previous VFW site in Front Royal - Assume 100 space lot can be accommodated. This land would require aquistion from the current property owner. As well, the area is on a wetland area and mitigation measures would be required. Both of these will greatly increase the cost (not included in construction cost shown).	42,500	100	An approximate 200' connection from the lot to trail would need to be provided	Area is not owned by Norfolk Souther or the Town of Front Royal, adquisition would be required.	\$ 3,230,000.00	\$ 4,040,000.00	\$ 807,500.00	\$ 1,010,000.00	\$4.0M - 5.1M		

10 Lot Estimate

# **Opinion of Probable Project Costs - September 2021**

# Non-inflated Costs are in FY2021 Dollars

Item	Description	Unit Quantity			Unit Cost	Extension				
	Mobilization Items									
	Mobilization	LS	1	\$	15,637	\$	15,637			
	CN Surveying	LS	1	\$	2,837	\$	2,837			
	MOBILIZATION SUB-TOTAL					\$	18,474			
	Maintenance of Traffic (MOT) Items									
	MAINTENANCE OF TRAFFIC (MOT) SUB-TOTAL					\$	-			
	Roadway Items									
10607	ASPHALT CONCRETE TY. SM-12.5A	TON	100	\$	133.00	\$	13,300			
10245	AGGR. BASE MATL. TY. I NO. 21B	TON	310	\$	37.00	\$	11,470			
	ROADWAY SUB-TOTAL					\$	28,690			
	Hydraulics Items									
	SWM / BMP	LS	1	\$	25,000.00	\$	25,000.00			
	E&S CONTROLS	LS	1	\$	6,000.00	\$	6,000			
	HYDRAULICS SUB-TOTAL					\$	31,000			
	In-Plan Utilities Items									
	IN-PLAN UTILITIES SUB-TOTAL					\$	-			
	Traffic Items									
	PAVEMENT MARKINGS	LS	1	\$	3,500.00	\$	3,500			
	TRAFFIC SUB-TOTAL					\$	3,500			
	Earthwork/Materials Items			·						
00120	REGULAR EXCAVATION	CY	300	\$	27.00	\$	8,100			
00140	BORROW EXCAVATION	CY	400	\$	45.00	\$	18,000			
00142	BORROW EXCAVATION MIN. CBR-20	CY	357	\$	45.00	\$	16,071			
	EARTHWORK/MATERIALS SUB-TOTAL					\$	42,171			
	Sound Wall Items			·						
	SOUND WALL SUB-TOTAL						-			
	Other Items			·						
00111	CLEARING AND GRUBBING	ACRE	0.10	\$	14,700.00	\$	1,470			
	LANDSCAPING	LS	1	\$	10,000.00	\$	10,000			
	SIGNS	EA	2	\$	500.00	\$	1,000			
	OTHER SUB-TOTAL					\$	12,470			
	MAJOR ITEMS SUBTOTAL					\$	136,000			
	Construction Totals			·						
	Unaccounted for Items (20%)	LS	1	\$	24,000	\$	24,000			
	Construction Contract Total					\$	160,000			
	Construction Contingency (30%)	LS	1	\$	48,000	\$	48,000			
	Contract Contingency (5%)	LS	1	\$	8,000	\$	8,000			
	Construction Engineering & Inspection (20%)	LS	1	\$	32,000	\$	32,000			
				<u> </u>	stion Dhose (in FV2021 Dellars)	-	249,000			

Total Construction Phase (in FY2021 Dollars) \$ 248,000

## **30 Lot Estimate**

# Opinion of Probable Project Costs - September 2021

# Non-inflated Costs are in FY2021 Dollars

Item	Description	Unit Quantity			Unit Cost	Extension			
	Mobilization Items								
	Mobilization	LS	1	\$	51,754	\$	51,754		
	CN Surveying	LS	1	\$	12,468	\$	12,468		
	MOBILIZATION SUB-TOTAL					\$	64,221		
	Maintenance of Traffic (MOT) Items								
	Roadway Items								
10607	ASPHALT CONCRETE TY. SM-12.5A	TON	180	\$	133.00	\$	23,940		
10245	AGGR. BASE MATL. TY. I NO. 21B	TON	780	\$	37.00	\$	28,860		
13220	HYDR. CEMENT CONC. SIDEWALK 4"	SY	150	\$	56.00	\$	8,400		
	ROADWAY SUB-TOTAL					\$	69,600		
	Hydraulics Items								
	SWM / BMP	LS	1	\$	50,000.00	\$	50,000.00		
	Storm Structures	EA	6	\$	5,500.00	\$	33,000.00		
	Storm Sewer	LF	300	\$	160.00	\$	48,000.00		
	E&S CONTROLS	LS	1	\$	25,000.00	\$	25,000		
	HYDRAULICS SUB-TOTAL					\$	156,000		
	In-Plan Utilities Items								
	IN-PLAN UTILITIES SUB-TOTAL					\$	-		
	Traffic Items					L			
	PAVEMENT MARKINGS	LS	1	\$	10,000.00	\$	10,000		
	Lighting	LS	1	\$	25,000.00	\$	25,000		
	TRAFFIC SUB-TOTAL					\$	35,000		
	Earthwork/Materials Items								
00120	REGULAR EXCAVATION	CY	800	\$	27.00	\$	21,600		
00140	BORROW EXCAVATION	CY	1,000	\$	45.00	\$	45,000		
00142	BORROW EXCAVATION MIN. CBR-20	CY	911	\$	45.00	\$	40,982		
	EARTHWORK/MATERIALS SUB-TOTAL					\$	107,582		
	Sound Wall Items								
	SOUND WALL SUB-TOTAL					\$	-		
	Other Items								
00111	CLEARING AND GRUBBING	ACRE	1.00	\$	14,700.00	\$	14,700		
	LANDSCAPING	LS	1	\$	25,000.00	\$	25,000		
	Rest Room	LS	1	\$	100,000.00	\$	100,000		
	SIGNS	EA	3	\$	500.00	\$	1,500		
	Drinking Fountains	EA	2	\$	5,000.00	\$	10,000		
	OTHER SUB-TOTAL					\$	151,200		
				·					
	MAJOR ITEMS SUBTOTAL					\$	584,000		
	Construction Totals								
	Unaccounted for Items (20%)	LS	1	\$	104,000	\$	104,000		
	Construction Contract Total					\$	688,000		
	Construction Contingency (30%)	LS	1	\$	207,000	\$	207,000		
	Contract Contingency (5%)	LS	1	\$	35,000	\$	35,000		
	Construction Engineering & Inspection (20%)	LS	1	\$	138,000	\$	138,000		
	•		T-4-1	<u> </u>	ction Phase (in FV2021 Dollars)	<u>,</u>	1 068 000		

Total Construction Phase (in FY2021 Dollars) \$ 1,068,000